

## **ND-01 NOTICE TO CONTRACTORS**

Effective immediately, the following will be accomplished by all Contractors before starting any work on NORTH DAVIS SEWER DISTRICT (DISTRICT) facilities.

### **1) GENERAL**

- a) District presence at pre-construction meetings is required prior to Contractor scheduling inspections. Contractor may schedule a separate pre-construction meeting with the District.
- b) No work shall commence on District sewers, directly or indirectly, without first having received authorization from the District.
- c) Point of Contact: Tyler Barfuss, 801-728-6815, 4252 W 2200 S, Syracuse, UT 84075.

### **2) HOURS OF OPERATION**

- a) The District's working hours are 7:00 a.m. to 4:30 p.m. MST, Monday through Friday. No sewer inspection will be done on weekends or holidays.
- b) The District reserves the right to bill overtime where District Staff are required to perform inspections after 4:30 p.m.
- c) Multiple inspection visits required for work that is incomplete, not to District standards, or not ready for inspection will result in additional time being billed to the Contractor.

### **3) SEWER LATERAL CONNECTIONS**

- a) No work shall begin until the proper fees for connection and inspection, plus impact fees as calculated by the City or District (whichever may apply), are paid and certified to the District as having been paid. The District only accepts cash or checks at the District office. Credit card payment can only be made online.
- b) No work shall begin until the proper building permits and licenses have been obtained from the City, County, or District.
- c) Minimum notice of 48 hours shall be given to the District prior to any work commencing or excavation being done on District-owned lines.
- d) No excavation or work shall be done on District-owned lines without the presence of a District Inspector.
- e) All sewer taps must be core drilled. The Contractor must accurately size and procure sewer taps based on the existing District's sewer (material and diameter) and the sewer lateral (material and diameter) to be connected. Sewer connections must be provided per standard details with approved products.
- f) 6" laterals shall be connected to 20" pipes or larger. Laterals larger than 6" shall be provided with a manhole unless authorized in writing by the District.

### **4) SETTING OF MANHOLES ON DISTRICT-OWNED SEWERS**

- a) Manholes are required to be set for connecting sewers or lateral sewer connections 8" or larger.
- b) No manholes shall be set on District-owned sewers without prior approval by the District.
- c) Manholes shall be precast components with precast base unless approved by the District.
- d) Contractors must submit design drawings and details of proposed manholes to be installed on District sewers for approval a minimum of 14 days prior to work commencing. Design drawings shall be submitted in PDF electronic format unless otherwise requested by the District.
- e) After approval of drawings, a minimum of 48 hours' notice shall be given to the District before any work commences directly or indirectly on District sewers. The manhole must be set in the presence of a District Inspector.
- f) Manhole construction on District-owned sewers shall be performed in accordance with Standard Detail ND-02.



**NORTH DAVIS SEWER DISTRICT**

---

## **ND-01 Notice to Contractors 1 of 2**

Adopted 6/13/2024

## **5) CONCRETE BATCHING**

- a) Ready-Mixed concrete shall be provided in accordance with ASTM C94 (Standard Specification for Ready-Mixed Concrete).
- b) The design water content of the mix (w/c ratio) shall not be exceeded. Addition of water, air entrainment, or superplasticizer shall only be performed by the Supplier. No additives shall be permitted without prior approval by the District.
- c) Non-air entrained concrete shall be discharged ninety (90) minutes after batching. Air entrained concrete or concrete that includes silica fume shall be discharged within sixty (60) minutes of batching.
- d) Requests for longer batching times shall be submitted and accepted by the District prior to procurement of concrete by the Contractor.
- e) The District shall not be responsible for the cost of rejected batches exceeding time limitations, loss of air entrainment, or slump.
- f) Where required, flowable fill shall be Type IL Portland cement per ASTM C595 with a compressive strength between 50 - 150 psi per ASTM D4318. No additives shall be permitted without prior approval by the district.

## **6) SEWER BYPASSING AND DEWATERING REQUIREMENTS**

- a) Where required, bypassing and sewer dewatering of District sewers shall be performed in accordance with Standard Detail ND-05.

## **7) ACCEPTANCE TESTING, FINAL COMPLETION, AND WARRANTY REQUIREMENTS**

- a) Acceptance testing, final completion, and warranty requirements shall be per Standard Detail ND-06.
- b) Failure of Contractors to comply with these requirements could result in the Contractor being barred from working on District sewers. If there are any questions on sewer ownership, please visit the District's Interactive Map at <http://www.ndsd.org> (See Map of District Pipes and Manholes).

