



NOTES:

1. GRADE RINGS SHALL BE POLYMER OR EPP. EPP GRADE RINGS SHALL BE SPIKED OR PINNED TO PREVENT MOVEMENT DURING BACKFILLING. GRADE RINGS AND FRAME MUST BE RAISED TO GRADE NO LATER THAN 2 WEEKS AFTER MANHOLE INSTALLATION.
2. FRAME AND COVER SHALL BE LOCATED DIRECTLY OVER THE INLET PIPE FOR SINGLE INLET AND OUTLET MANHOLES, UNLESS OTHERWISE DIRECTED BY THE DISTRICT.
3. PLACE AND COMPACT BACKFILL EQUALLY AROUND MANHOLE AND GRADE RINGS. BACKFILL WITH FLOWABLE FILL IF MANHOLE RISER OR CONE SECTIONS ARE EXPOSED OR ABOVE GRADE.
4. WHERE ADJUSTING EXISTING MANHOLE FRAME, COVER, AND GRADE RINGS TO FINISHED GRADE, GRADE RINGS MAY BE REPLACED-IN-KIND UNLESS OTHERWISE REQUIRED BY THE DISTRICT.
5. CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR PROPER BACKFILLING, COMPACTION, AND TESTING OF STREET SECTION AND MEET ALL RESTORATION REQUIREMENTS OF THE AGENCY, CITY, OR UDOT WHERE THE MANHOLE IS INSTALLED. CONTRACTOR MUST COORDINATE ANY ADDITIONAL INSTALLATION OR INSPECTION REQUIREMENTS WITH THE AGENCY.



NORTH DAVIS SEWER DISTRICT

ND-04 Manhole Cover and Grade Ring

Adopted 6/13/2024